

			Bidders	A & D Environmental	Advance One Development	Comanco Environmental	DOT Energy Solutions	Martin & Son Contracting
			Address	Lexington, SC	Charlotte, NC	Plant City, FL	Bethlehem, GA	Spartanburg, SC
Estimated Qty	Units	Unit Cost	Description	Extended Cost	Extended Cost	Extended Cost	Extended Cost	Extended Cost
0.45	Acres	Lump Sum	Site Preparation:	\$11,846.00	\$5,000.00	\$3,375.00	\$11,500.00	\$1,500.00
720	LF	Lump Sum	Excavation	\$27,808.00	\$32,000.00	\$8,640.00	\$22,500.00	\$7,200.00
720	LF	Lump Sum	Embankment (Compacted Soil)	\$13,861.00	\$7,200.00	\$3,600.00	\$6,500.00	\$7,200.00
1,040	CY	Lump Sum	Soil Hauling (excess Soil to Operating Landfill)	\$10,781.00	\$10,000.00	\$9,360.00	\$9,500.00	\$20,800.00
10,800	SF	Lump Sum	Geotextile	\$8,307.00	\$5,400.00	\$5,400.00	\$6,950.00	\$3,600.00
10,800	SF	Lump Sum	Geomembrane	\$12,927.00	\$10,800.00	\$10,800.00	\$12,500.00	\$6,480.00
1,040	CY	Lump Sum	Coarse Aggregate	\$40,441.00	\$45,000.00	\$52,000.00	\$65,502.00	\$41,600.00
720	LF	Lump Sum	PVC Pipe & Fittings - Perforated	\$9,603.00	\$12,500.00	\$17,280.00	\$8,246.00	\$17,280.00
112	LF	Lump Sum	PVC Pipe and Fittings- Solid	\$4,801.00	\$5,000.00	\$5,600.00	\$5,733.00	\$4,032.00
0.45	Acres	Lump Sum	Revegetation	\$2,689.00	\$5,000.00	\$6,750.00	\$4,500.00	\$4,500.00
1	LS	Lump Sum	Surveying	\$6,124.00	\$3,500.00	\$5,000.00	\$9,500.00	\$3,000.00
1	LS	Lump Sum	Bonds, Mobilization, & Insurance:	\$3,729.00	\$15,000.00	\$22,000.00	\$29,685.00	\$3,000.00
			TOTAL BASE BID PRICE	\$152,917.00	\$156,400.00	\$149,805.00	\$192,616.00	\$120,192.00
Alternate Bid Items								
	LF		Erosion Control (Silt Fence)	\$10.25	\$8.00	\$2.00	\$6.75	\$6.00
	LF		Additional Passive Landfill Gas Vent Trench	\$178.51	\$175.00	\$200.00	\$206.84	\$166.00